



## **BRUHAT BENGALURU MAHANAGARA PALIKE**

No: EE/P-E/QUT/ 21 /2013-14

Executive Engineer Project (East)  
21<sup>st</sup> floor P.U.Building,  
M G Road Bangalore-560001  
Date: 24/08/2013

### **Call For Competitive Rates through online**

Executive Engineer Project (East) invites competitive rates on behalf of Commissioner BBMP as per the KTPP act 2000 through online from government registered authorized companies, authorized dealers, sub dealers, who have adequate Experience and associated in providing and installing and commissioning of Washing Machines, Hydro Extractor, Tumble Drier etc for the works mentioned below.

SI No	Name Of work
1	Improvements of Vasanthnagar Dhobi Ghat in ward no 93
2	Improvements and up gradation of Ulsoor MV Garden Dhobi Ghat in ward no-90,

### **Details Specification and format is as follows.**

SI NO	Item of Work	Unit	Model No.	Rates Quoted (Inc of all tax.)	
				In Rupees	In Words
1	Providing, supplying, fixing and commissioning of 50 KGS HORIZONTAL WASHING MACHINE comprising of 900 x 1120 mm cylinder, 712 Ltr. Capacity cylinder, Door Opening size 440 x 470 mm, Water inlet of 2" x 1 No., Motor of 3 HP, Drain of 3 inch, Overall dimension of 1910 x 1380 x 1530 mm. Total Net weight of 740 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading , all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.	No	AWM-46		

2	<p>Providing, supplying, fixing and commissioning of 30 KGS HORIZONTAL WASHING MACHINE comprising of 790 x 900 mm cylinder, 440 Ltr. Capacity cylinder, Door Opening size 370 x 370 mm, Water inlet of 2" x 1 No., Motor of 2 HP, Drain of 3 inch, Overall dimension of 1690 x 1310 x 1330 mm. Total Net weight of 480 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading , all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.</p>	No	AWM-30		
3	<p>Providing, supplying, fixing and commissioning of 15 KGS HORIZONTAL WASHING MACHINE comprising of 600 x 700 mm cylinder, 230 Ltr. Capacity cylinder, Door Opening size 310 x 310 mm, Water inlet of 1-1/2" x 1 No., Motor of 1 HP, Drain of 1.5 inch, Overall dimension of 1120 x 1200 x1050 mm. Total Net weight of 300 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading , all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.</p>	No	AWM-15		
4	<p>Providing, supplying, fixing and commissioning of 50 KGS HYDRO EXTRACTOR comprising of SS of 304 grade Outer Drum, SS perforated &amp; SS 304 grade and 1.6 mm thickness Inner Basket, 900 x 350 mm dia Size Basket, 7.5 HP Extractor Motor,76.2 mm Dia Drain, Overall dimension 1800x1580x1020mm. Total Net Weight 750 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading , all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.</p>	No	WHE-46		
5	<p>Providing, supplying, fixing and commissioning of 30 KGS HYDRO EXTRACTOR comprising of SS of 304 grade Outer Drum, SS perforated &amp; SS 304 grade and 1.6 mm thickness Inner Basket, 710 x 340 mm dia Size Basket, 3 HP Extractor Motor, 50 mm Dia Drain. Overall dimension 1130 x 960 x 1220 mm. Total Net Weight 380 Kgs. Including the cost of all materials, labour, hire charges and making all</p>	No	WHE-46		

	loading and unloading , all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.				
6	Providing, supplying, fixing and commissioning of 25 KGS TUMBLE DRIER comprising of 538 Ltr. Basket Volume, 620 mm Door Opening, 2 HP Motor, Overall Dimension 1000 x 1450 x 1820 mm. Total Net Weight 490 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading, all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.	No	ATD-25		
7	Providing, supplying, fixing and commissioning of 50 KGS TUMBLE DRIER comprising of 1227 Ltr. Basket Volume, 750 mm Door Opening, 4 HP Motor, Overall Dimension 1360 x1990 x 2135 mm. Total Net Weight 785 Kgs. Including the cost of all materials, labour, hire charges and making all loading and unloading, all incidental charges and as per detailed ISI specification and directions of Engineer Incharge of work.	No	ATD-50		
8	Water Cooled developing 58 BHP @ 1500rpm, Coupled to 45KVA Alternator with Standard accessories like Battery with leads Exhaust Silencer, Control Panel, fuel Tank with CPCB approved Ref: NAL/MOES/SSPT-F3/2011/ 0394 dt: 27.06.2011	No	45KVA Model: SSPT- 45ES		

### **Time Schedule / Calendar of Events**

1. The detailed technical specification, model number etc., is available in office in working hours and in bbmp website [www.bbmp.gov.in](http://www.bbmp.gov.in) from 27/8/2013.
2. The rates should be submitted on or before 05/09/2013 upto 4.30 PM in the prescribed format to through mail. **Mail Address : [ee.peast@gmail.com](mailto:ee.peast@gmail.com)**
3. Opening of mail on 07/09/2013 at 5.00 PM in presents of bidders. (If possible)
4. Executive Engineer reserves rights to accept for reject of rates quoted by bidders.
5. Rates shall be inclusive of all taxes as per government latest orders.

Sd/-

**Executive Engineer Project (East)  
Bruhat Bangalore Mahanagara Palike**